

Drought Contingency Project Helps Two Cities Maintain Water Supply

Aaron D. Archer, P.E., *HDR*

Shay Roalson, P.E., *HDR*

Kenneth Wheeler, P.E., *City of Cedar Park*

Wayne Watts, P.E., *City of Leander*



Synopsis

- ❑ Background
 - Cedar Park and Leander WTPs
 - Lake Travis
- ❑ Design (Phase A & B)
- ❑ Schedule
- ❑ Financing
- ❑ Conclusions



Lake Travis, Austin, Texas (PHOTO BY CHASE A. FOUNTAIN/TEXAS PARKS AND WILDLIFE)
<http://www.flickr.com/photos/texasparkswildlife/with/6195917758/>


The Setting

- ❑ Cedar Park and Leander operate floating raw water intakes on Sandy Creek arm of Lake Travis
- ❑ The intakes are steel structures with polyethylene floats, deck, superstructure, vertical turbine pumps, and discharge hoses
- ❑ Combined firm capacity = 40 MGD
- ❑ Operation likely to begin to become impaired when water depth falls below 15 feet (WSE 615 ft-msl)

Cedar Park Intake – 26 MGD



Leander Intake – 14 MGD



The Setting

*~ 675 ft-msl
(6 ft below
conservation pool)*




*~ 629 ft-msl
(52 feet below
conservation pool)*



Lake Travis

- ❑ Mansfield Dam completed in 1941
- ❑ Lake Travis is the only Highland Lake specifically designed to contain floodwater
- ❑ Volume when full = 1.14 MAF
- ❑ Lakes Buchanan and Travis are the region's water supply reservoirs (2.01 MAF)




Lake Travis Water Management Plan

- ❑ LCRA operates the Highland Lakes in accordance with the TCEQ approved Water Management Plan (WMP)
- ❑ Key elements of the WMP:
 - Views Lakes Travis and Buchanan as a single water system
 - Determines the amount of firm and interruptible supply
 - Establishes Drought Management and Contingency Plans to define criteria for curtailment



Historical Lake Travis Water Level

All-time Low Lake Levels



<u>Year</u>	<u>Lake Level (ft-msl)</u>
1951	614.2
1963	615.0
2011	626.1
2009	629.8
1984	636.6
2000	640.2
2006	643.6

All-time Low

Monthly Inflows

<u>Month</u>	<u>Inflow (ac-ft)</u>
1952 - Aug	210
1964 - July	347
2011 - Aug	403
2011 - July	734
2011 - Sept	922
2011 - Jun	1,341
1954 - Aug	1,592

Level on January 24, 2012:
626.1 ft-msl (37% capacity)


LCRA Response: Drought Relief Plan

- ❑ TCEQ approved a LCRA petition to deviate from the WMP
- ❑ Prevents irrigation releases if combined storage is below 850,000 acre-feet on March 1, 2012
- ❑ Reduced release will be available for the first crop if combined storage is above 850,000 acre-feet on March 1
 - Releases only for first crop (second crop release subject to Board approval)
 - Releases would not begin till April 1 and not exceed 125,000 acre-feet
- ❑ Current combined storage is approximately 738,000 acre-feet



Long-term Solution

- ❑ Preliminary planning for a deep water intake started in 1998
- ❑ Brushy Creek Regional Utility Authority (BCRUA) – a regional partnership of the cities of Cedar Park, Round Rock, and Leander – created in 2006
- ❑ Phase 1 (floating intake, raw water transmission line, WTP) will be completed Spring 2012
- ❑ Phase 2 consists of a deep water intake to serve the BCRUA, Cedar Park, and Leander WTPs
- ❑ The deep water intake will secure access to a lakebed depth lower than the lowest level predicted by the LCRA WMP
- ❑ Due diligence is underway to finalize selection of a site for the deep water intake



Interim Solution

- ❑ Drought contingency plan needed
- ❑ Two-fold objective: reduce demand and maintain uninterrupted supply
- ❖ Demand reduction:
 - *Quantitative conservation goals*
 - *Inclined water use rate structure*
 - *Leak detection/repair program*
 - *Record management system*
 - *Rebate/incentives program*
 - *Water reuse program*
 - *4-stage drought response plan*
 - *Education and public outreach*
 - *Ad campaign*
 - *Water conservation coordinator*
 - *Best management practices*
- ❖ Uninterrupted water supply:
 - *Modify existing barges to operate at lowest possible lake level*
 - *Develop plan for a contingency raw water pump station and transmission pipeline*
 - *Cedar Park and Leander partnership*



Implementation Considerations

- ❑ Easement acquisition
- ❑ Public perception
- ❑ Safety
- ❑ Cost and cost-sharing
- ❑ Technical:
 - Pump station location
 - Pipeline alignment
 - Capacity
 - Maintaining operation of existing intakes during construction and startup



Location

- ❑ Principal drivers: depth and availability of power supply
- ❑ Lakebed bathymetry shows 20 ft additional depth gained moving 1 mile downstream.
- ❑ Additional 2 miles downstream (main lake body) for considerable depth gains (20+ ft)
- ❑ 3-phase power required for the selected raw water pumps
- ❑ Only one location on this arm of Lake Travis with existing three phase power – the same location as added 20 ft depth



Capacity

- ❑ Capacity should be selected with consideration of the demand it is likely to serve
- ❑ Implementation is made necessary by prolonged drought conditions so some level of demand management is anticipated
- ❑ LCRA cannot invoke mandatory curtailment of firm water demand unless a drought event is worse than the drought of record
- ❑ Nevertheless, the cities will have implemented mandatory drought response measures before it becomes necessary to pump from the contingency intake
- ❑ Studies on water use restrictions suggest a 20% demand reduction should be achievable
- ❑ Design pump station capacity = 30 MGD (Ultimate = 40 MGD)



Regulatory Approval

Approvals required from the following:

- ✓ LCRA
- ✓ TCEQ
- ✓ USACE
- ✓ JWSC
- ✓ COJ




- Performed habitat and archeological evaluations
- Notified agencies at the earliest possible date
- Met frequently and established clear lines of communication to ascertain major areas concern (e.g., navigational impacts)



Phase A Design


Phase A – Underwater Pipeline:

- Underwater steel header assembly
- Submarine transmission pipeline: 4,200 42-IN HDPE (DR 11)
- Concrete pipeline ballasts
- Initial delivery connections



Phase A Challenges

1. Header thrust restraint
2. Fusion joint integrity testing
3. Sandy Creek Marina
4. Submerged cliff transition



Phase B Design

Phase B– Floating Raw Water Intake:

- Produced in 4 Design Packages
- DP1: Modular barge, pumps and barge appurtenances
- DP2: Shoreside electrical
- DP3: Instrumentation and control
- DP4: Delivery connections



Phase B Challenges

1. Owner/Contractor Agreement

- Phase B done in accordance with Chapters 252.021 and 252.022 of Texas Local Government Code with an exemption to the competitive bidding requirements due to a procurement necessary to preserve or protect the public health
- Contact price based on preliminary schedule of values determined by HDR and Contractor
- Open book policy
- Competitive pricing obtained for major purchases and subcontracts and submitted for review/approval
- Contractor's fee set (payroll, material/equipment, subcontracts)



Phase B Challenges

2. Control strategy


- Delivering water to two WTPs at different hydraulic gradelines
- Cannot overflow the raw water tanks at either WTP
- Operate system by a pressure set point at higher elevation Leander WTP
- Influent level control valve at Leander WTP to prevent raw water tank overflows
- PRV/PSV at Cedar Park



Phase B Challenges

3. Public perception

- Noise emissions
- Title encumbrance
- Limited boat dock and water use due to restricted zone radius
- Permanent placement



Phase B Challenges


4. Pump procurement

- Solicited quotations via the contractor from Godwin and Pioneer
- Bid included lease and outright purchase options
- Lease bid based on initial 3 month period with buyout option or new rental rate after 3 months
- Negotiated percent of monthly lease rate to be applied to subsequent purchase after 3 months
- Negotiated cancellation fee schedule

godwin 
a xylem brand



Timing and Schedule



- Developed construction schedule and used LCRA long range lake level forecast to determine project trigger date
- LCRA forecast is a projection of the likelihood of future lake levels using a stochastic hydrology model
- Model prepares probability plots of the likelihood of exceedence

Timing and Schedule

- ❑ Current drought tracked the worst-case line so used this curve to establish the trigger date
- ❑ Substantial Completion: Phase A – April 16
Phase B – Dynamic (presently July 1)
- ❑ Deferred Phase B rental components
- ❑ Monthly hold and place charge negotiated with Godwin to extend cancellation fee schedule and secure equipment for allocation to the project
- ❑ Constructing all permanent underground infrastructure components



Financing

- ❑ Interlocal cost share agreement
- ❑ Cost allocation was based upon the pro-rata share of the design capacity
- ❑ Cedar Park managed administration of the project
- ❑ Funds contributed to a construction fund administered by Cedar Park
- ❑ System operated and maintained by Cedar Park upon completion
- ❑ O&M costs paid in accordance with pro-rata share



Summary Remarks

- ❑ Plan for the worst
- ❑ Design content must be complete but don't go beyond what is required
- ❑ Communication and cross-discipline coordination must be automatic
- ❑ In a case where competitive bidding is bypassed:
 - Pick the right contractor
 - Insure competition on major work items
 - Promote collaboration between designer and constructor
- ❑ Involve high-level decision makers early and often



Questions?

Aaron Archer, P.E.

HDR Engineering

aaron.archer@hdrinc.com



Extra Slides...



Project Costs

- ❑ Phase A – Underwater Pipeline: 3.6 MUSD
- ❑ Phase B – Floating Pump Station:
 - 3.0 MUSD (3 month rental)
 - 3.6 MUSD (6 month rental)



Lake Travis Simulated Elevation and Storage

